



Date: April, 2005

**Meadowood
Septic System Improvement Program
Town of Old Saybrook, CT**

| Legend | | # OF LOTS | % OF LOTS |
|--------------------------|---|---------------------------------|-----------|
| | AT System and Compact Leaching System Required (Leaching Area Available < 1/2 of PHC Requirement)..... | 0 | 0% |
| | AT System Required Due to Leaching Area Available (1/2 of PHC Required < Leaching Area Available < 2/3 of PHC Requirement)..... | 0 | 0% |
| | 2/3 PHC Requirement < Leaching Area Available < PHC Requirement..... | 0 | 0% |
| | Leaching Area Available > PHC Requirement..... | 72 | 100% |
| | AT System Required Due to Waterfront Lot..... | 3 | 4% |
| | Drywell Removal & Replacement with New Leaching System..... | 15 | 20% |
| | Undersized Septic Tanks..... | 1 | 1% |
| | Vacant Lots..... | 4 | |
| | Wetlands | | |
| PHC = Public Health Code | | | |
| | | Total Number of Developed Lots: | 74 |